
INSPIRE Installation Techniques – PACKAGING - TRANSPORT

Shutters are relatively fragile and are packaged substantially to prevent transport damage. Attention should always be paid to correct loading of vehicles to ensure no rubbing of hinges or part whilst in transport, use of foam or cardboard is recommended between panels and tie down belts. Getting the shutters and framing into the house is also transporting the goods, so the product should only be unpacked once on site or preferably once in the room in which it will be installed. This will prevent damaging the panels etc. on the walls and protect the customer's home.

The packaging should not be removed from the property until the shutters are installed and working properly. Reported missing components are generally found within the packaging, or in hardware boxes. In addition, in the unlikely event that the shutters need to be removed again from the house, the packaging can be used to prevent any further damage or issues.

A label will appear on each package that will provide all the information you will need to identify the parts inside, including room location and item numbers. This will allow you to move the correct components to the correct location without opening them first.

